

STATE OF NORTH CAROLINA  
 DIVISION OF HIGHWAYS  
 SUMMARY OF QUANTITIES

ITEM	SECT	QUANTITY	UNIT	ITEM DESCRIPTION	ITEM	SECT	QUANTITY	UNIT	ITEM DESCRIPTION
1	800	1	LS	MOBILIZATION	33	SP	300	LF	SAFETY FENCE
2	801	1	LS	CONSTRUCTION SURVEYING	34	1630	5	CY	SILT EXCAVATION
3	SP	1	LS	REINFORCED BRIDGE APPROACH FILL -LREV- STA 16+55.11	35	1631	535	SY	MATTING FOR EROSION CONTROL
4	226	1	LS	GRADING	36	1632	160	LF	1/4" HARDWARE CLOTH
5	226	200	CY	UNDERCUT EXCAVATION	37	SP	80	SY	FLOATING TURBIDITY CURTAIN
6	SP	20	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	38	1660	1	ACRE	SEEDING AND MULCHING
7	SP	40	SY	FOUNDATION CONDITIONING FABRIC	39	1661	50	LB	SEED FOR REPAIR SEEDING
8	SP	30	LF	18" CAA PIPE CULVERTS, 0.064" THICK	40	1661	0.2	TON	FERTILIZER FOR REPAIR SEEDING
9	SP	68	LF	24" CAA PIPE CULVERTS, 0.064" THICK					
10	610	60	TON	ASPHALT CONCRETE BASE COURSE, TYPE B25.0B	41	402	1	LS	REMOVAL OF EXISTING STRUCTURE AT -L- STA 16+55
11	610	260	TON	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 119.0B	42	412	1	LS	UNCLASSIFIED STRUCTURE EXCAVATION
12	610	300	TON	ASPHALT CONCRETE SURFACE COURSE, TYPE 59.5B	43	420	26.6	CY	CLASS AA CONCRETE (BRIDGE)
13	620	38	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	44	422	1	LS	BRIDGE APPROACH SLABS
14	840	2	EA	MASONRY DRAINAGE STRUCTURES	45	425	3894	LB	EPOXY COATED REINFORCING STEEL (BRIDGE)
15	840	2	EA	FRAME WITH GRATE, STD 840.29	46	450	800	LF	HP 12 X 53 GALVANIZED STEEL PILES
16	846	70	LF	SHOULDER BERM GUTTER	47	450	10	EA	PILE REDRIVES
17	862	264	LF	STEEL BEAM GUARDRAIL	48	SP	130.25	LF	VERTICAL CONCRETE BARRIER RAIL
18	862	10	EA	ADDITIONAL GUARDRAIL POSTS	49	430	1	LS	ELASTOMETRIC BEARINGS
19	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	50	430	650	LF	3'-0" X 2'-0" PRESTRESSED CONCRETE CORED SLABS
20	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	51	SP	1	EA	PDA TESTING
21	876	5	TON	RIP RAP, CLASS I	52	SP	1	EA	PDA ASSISTANCE
22	876	80	TON	RIP RAP, CLASS II					
23	876	5	TON	RIP RAP, CLASS B					
24	876	150	SY	FILTER FABRIC FOR DRAINAGE					
25	1605	1080	LF	TEMPORARY SILT FENCE					
26	1610	10	TON	STONE FOR EROSION CONTROL, CLASS B					
27	1610	63	TON	SEDIMENT CONTROL STONE					
28	1615	1	ACRE	TEMPORARY MULCHING					
29	1620	50	LB	SEED FOR TEMPORARY SEEDING					
30	1620	0.2	TON	FERTILIZER FOR TEMPORARY SEEDING					
31	1622	200	LF	TEMPORARY SLOPE DRAINS					
32	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS					

REVISIONS

09/06/11 Remove Line Item #41 (Relocate Existing 6" Water Main)